CHITALDRUG DIVISION.

Dated 17th January 1910.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 5th February 1910, for constructing a new additional block for the High School at Chitaldrug. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1910.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 (one hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new additional block for the High School at Chitaldrug" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Constructing a new additional block for the High School at Chitaldrug.

No.	*Details of work.*	*Per*	*Quantity.*
1.	Clearing side	Lump sum	
2.	Earthwork	C. yds.	282
3.	Foundation with fort stone in mortar	C. ft.	6,978
4.	Basement with dressed fort stone in mortar	„	2,623
5.	Burnt brick in mortar or burnt stone in mortar, superstructure including scaffolding	„	7,153
6.	Arch work	„	124
7.	Burnt stone slabs roughly dressed 6″ thick	S. ft.	1,536
8.	Burnt or raw stone pillars dressed complete with capitals, base, etc.	R. ft.	160
9.	Teakwood doors, pannelled (4′×7′) inside with locks, bolt, hinges, etc., complete	Sq. ft.	338
10.	Teakwood windows with pannelled and glazed shutters inside and iron bars etc.	„	441
11.	Teakwood ventilators with glazed shutters, ropes, etc., complete	„	142
12.	Plastering with mortar	Sqrs.	104·84
13.	Pointing with cement	„	10·25
14.	Cornice work	R. ft.	490
15.	Flooring with Cuddapah slabs over 3″ concrete and cement pointing complete	Sqrs.	33·36
16.	White and colour-washing	„	104·84
17.	Wood oiling to doors and windows	„	9·20
18.	Teakwood gate with iron bars $\frac{3}{4}$″ diameter and painting, etc., complete	S. ft.	80
19.	Chocolate or silicate painting to doors and windows	Sqr.	9·20
20.	Teakwood screen, etc., complete	S. ft.	162
21.	Teakwood wrought and put up with wood-oiling including beams	C. ft.	979
22.	Roofing with pukka terrace	Sqr.	31·29
23.	Brick-in-chunam parapet and building wall	R. ft.	526
24.	Bengal terrace	Sqr.	13·88
25.	Eave-board, teakwood	R. ft.	150

C. KRISHNA IYENGAR,
Executive Engineer.